

Mass concrete in Indian Metros

Design and Execution engineered

G.Sivakumar

sivakumar@icomat.in

Services in Curated Concrete

Functional requirements of Mass Raft Structure

- Larger in size yet monolithic in nature
- As homogeneous as possible though concrete is heterogenous
- Fully compacted mass devoid of pores, voids and cracks having a volume that is equivalent to a residential apartment or more, with rebar cage

Mass concreting of Raft Structure has twin challenges in India

- Mitigating Temperature effects
 - Controlling Peak temperature & Temperature difference
- Making the structure as monolithic as possible
 - Planning & execution of sequence of casting

Challenge in Mass Concreting in Indian Metros – constraints

- Capacity of Plants – lower per hour production capacity
- Predominantly line pump utilization with very few Boom placers in use
- Transit mixers deployment, based on daily average, would be less in number to cater to the added volume required for mass concreting
- Need to use multiple plants for delivery that in turn results in scarcity of high-skilled Quality Control personnel
- Lower stock capacity to store materials required for mass concreting
- Issues with traffic ➔ Restricted timing, routes, Congestion, etc
- Possibility of abrupt stoppage of delivery of concrete for various reasons
- Site location and its narrow accessibility result in limited scope for multi-front delivery of concrete loads

Capabilities abroad - Achievements

- 20,246 cum in 62 hours in Sharjah (April 13 to 16 2017)
- 19,624 cum in 49 hours (Lakhta Centre Tower, Russia in March 1 2015)
- 16,208 cum in 18.5 hours in Los Angeles (February 16 2014)
- 5500 cum of M80 grade in 37 hours Singapore (April 2019)
 - M80 requires more time to produce and it is a very sensitive concrete

Capabilities abroad – USA, better resources & accessibility



Capabilities abroad – Russia, better resources & accessibility




Scenario in India

- Supplying 1000 cum/day is considered good
- 2000 cum/day is considered as the best effort with 3 or more plants supplying
- Hence, casting of a raft structure with a volume of 5000 cum would require about minimum 3 days duration
- Cold joints are unavoidable, though manageable
- If planned for horizontal joint over vertical joint, there are distinct advantages

Scenario in India - Casting 65.0 m X 41.0 m X 1.8 m size raft

- Raft with a volume of about 4800 cum of concrete is to be cast in 3 days
- Temperature controlled concrete is to be used, with addition of Ice, Chilled water, Supplementary Cementitious Material and Retarding admixture. Super-plasticizer is to be added for workability
- With three layers, expected time lapse between the successive layers is from 10 to 20 hours
- Horizontal layering, a proven practice, is preferable compared to casting thicker layers that would leave vertical joints, especially at the bottom (refer to Pics)
- Temperature Controlled Mass concrete, invariably cast with Fly Ash / GGBS and with retarder component is expected to exhibit a final setting time of more than 12 hours

A typical Casting Scenario – 4800 m³ @ 80 m³/hr with 4 pumps in operation – 3 X 0.6m layers



- Time lapse between 1st and 2nd layer initially 10 hours and finally 20 hours
- Time lapse between 2nd and 3rd layer initially 20 hours and finally 10 hours

Casting in Layers

- Necessity, Concerns and Solutions

Casting in Layers - Necessity

- It is not possible to compact a layer which is more than 600mm thick with needle vibrators as the vibration would not travel deeper
- Slump value of 180 – 200 mm is required to ensure fresh concrete flows below and within the bottom rebars that are in two or more layers
- More importantly, spreading the thickness in layers of 0.5 to 0.6m would make compaction much easier, and visual inspection of a flat compacted surface is much more effective
- When cast in thicker layer ($>0.60\text{m}$) fresh concrete would slide with varying contour profile for a wider area (refer to Pics)
- Very often, the portions spread with varying thickness for a wider area would not get compacted because the focus would be on concrete that is getting pumped in the current portion to build the height

Casting in Layers - Necessity

- Casting in thicker layers/sections would also lead to un-intended and un-noticed vertical cold-joint formation due to concrete spreading in varying contours (refer to Pics)
- Even when a vertical joint is planned, formation of gap at the bottom due to differential shrinkage of hardened concrete on either side of the joint should be taken care of.
- A Vertical joint should be treated or provisioned to ensure that it remains water tight forever. Provision of water proofing membrane at the bottom may not be 100% fool-proof as experienced in the field
- If the thicker layer is poorly compacted due to difficulty in accessibility , resultant weak, porous portions and gaps (due to vertical joint) at the bottom pose great threat to durability as well as strength of the raft

Making the successive layers monolithic - Concern

➤ Structural Concern

- ❖ Cold joint formation leading to “Shear slip/failure” between the two successive layers
- ❖ Shrinkage cracks occurring on the surface of intermediate layer

Factors addressing about concern


- ✓ Shear due to lateral force is considered non-critical normally, due to the size of the mass raft, that is considered infinite in design aspect
- ✓ Leaving lateral construction joints, that form cold joints in walls which are pure flexural members, are routine practices in construction.
- ✓ When executed properly the horizontal joint in a raft, which is less critical would not exhibit any sign of slippage or cracking.

Courtesy : Er.Jegatheesan, Buro Engineers

Making the successive layers monolithic - Solution

➤ Solution

- ❖ Raft is expected to act like a continuous beam with a combination of Sagging (due to column's vertical load) and Hogging Bending moments
- ❖ Rebars of columns act as shear keys in the area around the columns
- ❖ Rebars in the form of Chair rods provided, act as shear keys across the area away from the column rebars
- ❖ Additional vertical hooks can be provided as shear keys, where essential. These vertical hooks shall run from top to bottom.
- ❖ Provision of additional nominal reinforcement in lateral directions, just below the joints would mitigate shrinkage cracks



Courtesy : Er.Jegatheesan, Buro Engineers


Making the successive layers monolithic - Solution




Column rebar forming Shear-keys in Raft

Making the successive layers monolithic - Solution

- Solution in the form of structural design



Making the successive layers monolithic - Solution




SC Square

Practices to adopt

Services in Curated Concrete


Practices to adopt – Better workability to send concrete beneath rebars



Multi layered rebars at the bottom of raft

Bottom-most rebar : Adequate slump ensuring concrete “Covering the Cover”

Practices to adopt – Addition of Retarding admixture to reduce Peak temperature of concrete



- Addition of retarding admixture shall be made essential in Mass concrete, especially when PCE based admixture is used.
- While PCE based admixture has the tendency to show “sudden withdrawal effect” leading to faster reaction of cement particles, Retarders tends to work to nullify the faster reaction.
- SNF with inbuilt retarder can also be considered.

Practices to adopt - Layer by layer casting – A way to build a concrete mass




- Layer by layer casting with a slump value of 180mm to 200mm, will make compaction easier and effective
- Horizontal & Flat spread with uniformity in appearance of the compacted surface ensures casting of a solid & water tight structure

SC Square

Practices to avoid

Services in Curated Concrete

Practices to avoid – Avoid low slump



- A slump of 120mm would not be adequate even to send the fresh concrete in from the top.
- At low slump the concrete would not reach the bottom of the rebar network, and a proper compaction of a wider area at the depth of $>1.0\text{m}$ is impossible.
- End result would be formation of porous structure that leads to seepages / leakages

Practices to avoid – Casting a thick layer (>0.6m)



- Attempt to cast a thicker layer would make fresh concrete spread haphazardly with lesser scope of ensuring compaction for such wider spread
- Unevenly spread concrete for a longer distance that remains uncompacted, would harden leaving weak and porous spots

Practices to avoid – Casting a thick layer ($>0.6\text{m}$)




- An image of uneven spread of concrete when attempted to cast a thicker layer ($>0.6\text{m}$)
- Concrete getting hardened in some places before compaction, creating porous and weak spots

Practices to avoid – Casting a thick layer (>0.6m)



- An image of uneven spread from a thicker layer (>0.6m) hardening before compaction
- Creation of un-intended vertical joint at the bottom as well as porous and weak spots

Layered concrete – Measurable approach with additional rebars between the layers





- ❖ Construction is a layered approach
- ❖ Let it start from the foundation

- G.Sivakumar

Head - ICOMAT & SC Square